

Schedule – C

(See Clause 2.1)

PROJECT FACILITIES

1 Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- a) Roadside Furniture;
- b) Tree Plantation;
- c) Others to be specified

2 Description of Project Facilities

Each of the Project Facilities is described below showing:

a) Toll Plaza : NIL

b) Road side Furniture

(i) Traffic Signs and Pavement Markings:

Traffic signs and pavement markings shall include road side signs, overhead signs, curve mounted signs and road marking along the project highway. The locations for these provisions shall be finalized as per manual.

(ii) Concrete Crash Barrier, Metal beam crash barrier, Separators (MS railings) wherever required as per manual.

(iii) Traffic Safety Devices wherever required

(iv) Boundary Stones

(v) Hectometer / Kilometer Stones

(vi) Fluorescent strips have to be provided at sites requiring safety and protection.

(vii) Overhead signs: To be provided at one locations i.e. at 0/00 (Wokha) as per IRC 67

(viii) Delineators and Studs: Nil

c) Pedestrian Facilities

Footpath on covered Drain have been provided at the following stretches:

SI No	Chainage from	Chainage to	Width of drain
1	0	150	1.0 m on both side
2	12000	14100	
3	22400	23600	

d) Landscaping and Tree Plantation: Nil

e) Truck lay byes: Nil

f) Bus-bays and Bus Shelter: Nil