

VOLUME – II
PERCENTAGE BOQ

Validate

Print

Help

[Percentage BoQ](#)

Tender Inviting Authority: NHIDCL

Name of Work: Repair and Maintenance of National Highway (NH 37) Dibrugarh Bypass (Including Dibrugarh Town) (Km. 581.700 to Km. 603.000) (Percentage Rate and Work Order Basis)

Contract No: NHIDCL/RO-NE/AS/Maint./NH37/2017-18/9

Bidder Name :					
PRICE SCHEDULE					
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)					
NUMBER #	TEXT #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	5	6	53	55
1	Water Bound Macadam for the pot holes filling	Nos	0.00	2939475.00	INR Twenty Nine Lakh Thirty Nine Thousand Four Hundred & Seventy Five Only
2	Prime Coat	Nos	0.00	523600.00	INR Five Lakh Twenty Three Thousand Six Hundred Only
3	Tack coat	Nos	0.00	1439900.00	INR Fourteen Lakh Thirty Nine Thousand Nine Hundred Only
4	Bituminous Macadam for pot hole filling	Nos	0.00	5917450.00	INR Fifty Nine Lakh Seventeen Thousand Four Hundred & Fifty Only
5	Bituminous Macadam for overlay	Nos	0.00	44380875.00	INR Four Crore Forty Three Lakh Eighty Thousand Eight Hundred & Seventy Five Only
6	Semi Dense Bituminous Concrete	Nos	0.00	30691237.50	INR Three Crore Six Lakh Ninety One Thousand Two Hundred & Thirty Seven and Paise Fifty Only
7	Road Marking	Nos	0.00	1113750.00	INR Eleven Lakh Thirteen Thousand Seven Hundred & Fifty Only
Total in Figures				87006287.50	INR Eight Crore Seventy Lakh Six Thousand Two Hundred & Eighty Seven and Paise Fifty Only
Quoted Rate in Figures		Select		0.00	INR Zero Only

Quoted Rate in Words	
----------------------	--

INR Zero Only

- NOTE: Bidder has to quote % above or below and quoted rates in figures & words will be auto generated which shall be binding on the bidder to agree the amount to work.

[Validate](#)[Print](#)[Help](#)[Item Wise BoQ](#)

Tender Inviting Authority: NHIDCL

Name of Work: Repair and Maintenance of National Highway (NH 37) Dibrugarh Bypass (Including Dibrugarh Town) (Km. 581.700 to Km. 603.000) (Percentage Rate and Work Order Basis)

Contract No: NHIDCL/RO-NE/AS/Maint./NH37/2017-18/9

Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT
1	2	4	5	6	53	55
1	Water Bound Macadam for the pot holes filling Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surfaces, backfilling the pot holes with WBM material. (thickness 75 mm in one layer)	1050.000	cum	2799.50	2939475.00	INR Twenty Nine Lakh Thirty Nine Thousand Four Hundred & Seventy Five Only
2	Prime Coat: Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.60 kg/sqm using mechanical means.	14000.000	sqm	37.40	523600.00	INR Five Lakh Twenty Three Thousand Six Hundred Only
3	Tack coat: 'Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom	119000.000 0	sqm	12.10	1439900.00	INR Fourteen Lakh Thirty Nine Thousand Nine Hundred Only

4	Bituminous Macadam for pot hole filling Providing and laying dense bituminous macadam (thickness 50mm) with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder transporting the hot mix to work site,laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment,rolling with smooth wheeled,vibratory and tandem rollers to achieve the desired compaction.	700.000	cum	8453.50	5917450.00	INR Fifty Nine Lakh Seventeen Thousand Four Hundred & Fifty Only
5	Bituminous Macadam for overlay Providing and laying dense bituminous macadam (thickness 50mm) with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder transporting the hot mix to work site,laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment,rolling with smooth wheeled,vibratory and tandem rollers to achieve the desired compaction.	5250.000	cum	8453.50	44380875.00	INR Four Crore Forty Three Lakh Eighty Thousand Eight Hundred & Seventy Five Only
3	Semi Dense Bituminous Concrete-25 mm Providing and laying dense bituminous concrete with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder@ 4.5 to 5 % of mix and filler (cement) transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment,rolling with smooth wheeled,vibratory and tandem rollers to achieve the desired compaction.	2625.0000	cum	11691.90	30691237.50	INR Three Crore Six Lakh Ninety One Thousand Two Hundred & Thirty Seven and Paise Fifty Only
3	Road Marking: Road marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface -Providing and laying of Hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads @250 gms per sqm, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. the finished surface to be level, uniform and free from streaks and holes.	1350.0000	cum	825.00	1113750.00	INR Eleven Lakh Thirteen Thousand Seven Hundred & Fifty Only
Total in Figures					87006287.50	INR Eight Crore Seventy Lakh Six Thousand Two Hundred & Eighty Seven and Paise Fifty Only
Quoted Rate in Words		INR Eight Crore Seventy Lakh Six Thousand Two Hundred & Eighty Seven and Paise Fifty Only				