

Schedule – C

(See Clause 2.1)

PROJECT FACILITIES

1 Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- a) Roadside Furniture;
- b) Tree Plantation;
- c) Others to be specified

2 Description of Project Facilities

Each of the Project Facilities is described below showing:

a) Toll Plaza : NIL

b) Road side Furniture

(i) Traffic Signs and Pavement Markings:

Traffic signs and pavement markings shall include road side signs, overhead signs, curve mounted signs and road marking along the project highway. The locations for these provisions shall be finalized as per manual.

(ii) Concrete Crash Barrier, Metal beam crash barrier, Separators (MS railings) wherever required as per manual.

(iii) Traffic Safety Devices wherever required

(iv) Boundary Stones

(v) Hectometer / Kilometer Stones

(vi) Fluorescent strips have to be provided at sites requiring safety and protection.

(vii) Delineators and Studs: Nil

c) Pedestrian Facilities

Footpath on covered have been provided at the following stretches.

SI No	Chainage from	Chainage to	Width of drain
1	32100	32400	1.0 m on both side
2	39800	40150	
3	40750	40850	
4	41200	41350	

d) Landscaping and Tree Plantation Nil

e) Truck lay byes: Nil

f) Bus-bays and Bus Shelter: Nil