

राष्ट्रीय राजमार्ग एवं अवसंरचना विकास निगम लिमिटेड

सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार
तीसरी मंजिल, पीटीआई बिल्डिंग, 4-संसद मार्ग, नई दिल्ली-110001

National Highways & Infrastructure Development Corporation Limited

Ministry of Road Transport & Highways, Govt. of India
3rd Floor, PTI Building, 4-Parliament Street, New Delhi-110001. +91 11 23461600, www.nhidcl.com

(भारत सरकार का उद्यम)



BHARATMALA
ROAD TO PROSPERITY



BUILDING INFRASTRUCTURE - BUILDING THE NATION
CIN: U45400DL2014GOI269062

(A Government of India Enterprise)

NHIDCL/Manipur/NH-102A/UTT/2021/PKG-2/3328 Dated: 13.01.2023
E-197796

To,
All the Prospective Bidders

Name of Work: Widening to 2 (Two) Lane with Hard shoulder road of Ukhrul – Toloi -Tadubi section of NH-102A from Design Chainage km 9.450 to km 50.850 (Package-2) in the State of Manipur on EPC mode .

Tender ID: 2022_NHIDC_726584_1

Corrigendum No -1

Sr. No	Reference	Existing Provision	Modified Provision
1	Schedule-H Table - 1.3.1 Payment procedure for "B.1- Reconstruction/New2-Lane Realignment/ Bypass (Flexible Pavement)"	Unit of measurement is linear length. Payment of each stage shall be made on pro-rata basis on completion of a stage in full length or 5 km length, whichever is less."	Please refer modified Schedule-H in this regard.
2	RFP Section 7, Clause 1, Bidding Schedule (Refer Clauses 1.1.5, 1.3, 2.11.4 (i), 2.12, 2.13, 2.14.2.3, 2.15.2 & 3.1.1)	Bid Due date: 13.01.2023 (1100 Hrs)	Bid Due date: 30.01.2023 (1100 Hrs)
		Bid Opening Date: 16.01.2023 (1130 Hrs)	Bid Opening Date: 31.01.2023 (1130 Hrs)

(Rajpal Singh)
Dy. General Manager (Tech.)

Schedule - H

(See Clauses 10.1 (iv) and 19.3)

Contract Price Weightages

1.1 The Contract Price for this Agreement is Rs. ****

1.2 Proportions of the Contract Price for different stages of Construction of the Project Highway shall be as specified below:

Item	Weightage in % of CP	Stage for Payment	Percentage
1	2	3	4
Road Works including Culverts, widening and repair of culverts	68.77 %	A- Widening and strengthening of existing road	
		(1) Earthwork up to top of the sub- grade	[Nil]
		(2) Sub-base Course	[Nil]
		(3) Non bituminous Base course	[Nil]
		(4) Bituminous Base course	[Nil]
		(5) Wearing Coat	[Nil]
		(6) Widening and repair of culverts	[Nil]
		B.1-Reconstruction/New 2-Lane Realignment / Bypass (Flexible Pavement)	
		(1.1) Earthwork up to top of the sub-grade: Hill Cutting (40% weightage of 55.5%)	22.2%
		(1.2) Earthwork up to top of the sub-grade: Construction of Subgrade (60% weightage of 55.5%)	33.3%
		(2) Sub-base Course	15.41%
		(3) Non bituminous Base course	8.24%
		(4) Bituminous Base course	0.71%
		(5) Wearing Coat	6%
		B.2- Reconstruction/New 8-Lane Realignment/ Bypass (Rigid Pavement)	
		(1) Earthwork up to top of the sub- grade	[Nil]
		(2) Sub-base Course	[Nil]
		(3) Dry Lean Concrete (DLC) Course	[Nil]
		(4) Pavement Quality Control (PQC) Course	[Nil]
		C.1- Reconstruction/ New Service Road (Flexible Pavement)	
		(1) Earthwork up to top of the sub- grade	[Nil]
		(2) Sub-base Course	[Nil]
		(3) Non bituminous Base course	[Nil]
		(4) Bituminous Base course	[Nil]
		(5) Wearing Coat	[Nil]
		C.2- Reconstruction/New Service Road (Rigid Pavement)	
		(1) Earthwork up to top of the sub- grade	[Nil]
		(2) Sub-base Course	[Nil]
(3) Dry Lean Concrete (DLC) Course	[Nil]		
(4) Pavement Quality Control (PQC) Course	[Nil]		
D- Reconstruction & New Culverts on existing road, realignments, bypasses Culverts (length <6m)	14.14%		

Schedule-H (PKG-II)

Minor bridge/ Underpasses/ Overpasses	0.00 %	A.1-widening and repairing of Minor Bridges (length >6 m & <60m)	
		Minor Bridges	[Nil]
		A.2- New Minor bridges (length >6 m and <60m)	



		(1) Foundation + Sub-Structure: On completion of the foundation work including foundations for wing and return walls, abutments, piers up to the abutment/pier cap.	[Nil]
		(2) Super-structure: On completion of the super-structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barriers, road, signs & markings, tests on completion etc. complete in all respect.	[Nil]
		(3) Approaches: On completion of approaches including Retaining walls, stone pitching, protection works complete in all and fit for use	[Nil]
		(4) Guide Bunds and River Training Works: On completion of Guide Bunds and river training works complete in all respects	[Nil]
		B.1- Widening and repairs of underpasses/overpasses	
		Underpasses/ Overpasses	[Nil]
		B.2-NewUnderpasses/Overpasses	
		(1)Foundation + Sub-Structure: On completion of the foundation work including foundations for wing and return walls, abutments, piers up to the abutment/pier cap.	[Nil]
		(2)Super-structure: On completion of the super-structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barriers, road signs & markings, tests on completion etc. complete in all respect. Wearing Coat (a) in case of Overpass-wearing coat including expansion joints complete in all respects as specified and (b) in case of underpass-rigid pavement including drainage facility complete in all respects as specified.	[Nil]
		(3) Approaches: On completion of approaches including Retaining walls/ Reinforced Earth walls, stone pitching, protection works complete in all respect and fit for use.	[Nil]
bridge(length>60 m)works and ROB/RUB/elevated sections/flyovers including viaducts, if any	3.62 %	(1)Foundation	[Nil]
		(2)Sub-structure	[Nil]
		(3)Super-structure(including bearings)	[Nil]
		(4)Wearing Coat including expansion joints	[Nil]
		(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]
		(6) Wing walls/return walls	[Nil]
		(7)Guide bunds, River Training works etc.	[Nil]
		(8)Approaches(including Retaining walls, stone pitching and protection works)	[Nil]
		A.2-New Major Bridges	
		(1)Foundation	18.16%

	(2)Sub-structure	51.26%
	(3)Super-structure (including bearings)	24%
	(4)Wearing Coat including expansion joints	2.72%
	(5)Miscellaneous Items like handrails, crash barrier, road markings etc.	1.28%
	(6) Wing walls/return walls	[Nil]
	(7)Guide bunds, River Training works etc.	[Nil]
	(8)Approaches(including Retaining walls, stone pitching and protection works)	2.58%
	B.1-Widening and repairs of (a) ROB (b) RUB	
	(1) Foundations	[Nil]
	(2) Sub-Structure	[Nil]
	(3) Super-Structure (Including bearings)	[Nil]
	(4)Wearing Coat(a)in case of ROB- wearing coat including expansion joints complete in all respects as specified and (b) incase of RUB-rigid pavement under RUB including drainage facility complete in all respects as specified	[Nil]
	(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]
	(6) Wing walls/Return walls	[Nil]
	(7) Approaches (Including Retaining walls, Stone Pitching and protection works)	[Nil]
	B.2-NewROB/RUB	
	(1)Foundations	[Nil]
	(2) Sub-Structure	[Nil]
	(3) Super-Structure (Including bearings)	[Nil]
	(4)Wearing Coat (a) in case of ROB- wearing coat including expansion joints complete in all respects as specified and (b) incase of RUB-rigid pavement under RUB including drainage facility complete in all respects as specified	[Nil]
	(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]
	(6) Wing walls/Return walls	[Nil]
	(7)Approaches (including Retaining walls/Reinforced Earth wall, stone pitching and protection works)	[Nil]
	C.1- Widening and repair of Elevated Section/Flyovers/Grade Separators	
	(1) Foundations	[Nil]
	(2) Sub-Structure	[Nil]
	(3)Super-Structure(Including bearings)	[Nil]
	(4)Wearing Coat including expansion joints	[Nil]
	(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]
	(6) Wing walls/Return walls	[Nil]
	(7)Approaches (including Retaining walls/Reinforced Earth wall, stone pitching and protection works)	[Nil]
	C.2- New Elevated Section/Flyovers/Grade Separators	
	(1) Foundations	[Nil]

		(2) Sub-Structure	[Nil]
		(3) Super-Structure (Including bearings)	[Nil]
		(4) Wearing Coat including expansion joints	[Nil]
		(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]
		(6) Wing walls/Return walls	[Nil]
		(7) Approaches (including Retaining walls/Reinforced Earth wall, stone pitching and protection works)	[Nil]
Other Works	27.61 %	(i) Toll Plaza	[Nil]
		(ii) Road side drains	20.344%
		(iii) Road signs ,markings, km stones, safety devices etc	5.035%
		(iv) Project facilities	
		a) Bus Bays	0.194%
		b) Truck Lay-byes	0.692%
		c) Passenger Shelter	0.08%
		d) Rest Area	[Nil]
		e) Diversion Works	[Nil]
		(v) Road side Plantation	[Nil]
		(vi) Repair of Protection Works other than approaches to the bridges, elevated sections/flyover/grade separators and ROB/ RUBs	[Nil]
		(vii) Safety & Traffic Management during const.	[Nil]
		(viii) Breast Wall	17.569%
		(ix) Toe Wall	[Nil]
		(ix) Gabion Structure	17.203%
		(x) Retaining Wall	13.982%
(xi) "W" : Metal Beam Crash Barrier	1.744%		
(xi) Parapet Wall	3.815%		
(xii) Site Clearance & Dismantling	1.503%		
(xiii) Protection Works (Seeding and Mulching, Turfing and Slope Protection with Soil Nailing & Coir Mat)	16.873%		
(xiv) Utility Shifting	0.966%		

1.3 Procedure of estimating the value of work done

1.3.1 Road works

Procedure for estimating the value of road work done shall be as follows:

Table 1.3.1

Stage of Payment	Percentage weightage	Payment Procedure
A- Widening & Strengthening of road		
(1) Earthwork up to top of the sub-grade	[Nil]	Unit of measurement is linear length. Payment of each stage shall be made on pro-rata basis on completion of a stage in a length of not less than 10 (Ten) percent of the total length.
(2) Sub-base Course	[Nil]	
(3) Non bituminous Base course	[Nil]	
(4) Bituminous Base course	[Nil]	
(5) Wearing Coat	[Nil]	
(6) Widening and repair of culverts	[Nil]	
B.1- Reconstruction/New 2-Lane Realignment/Bypass (Flexible Pavement)		
(1.1) Earthwork up to top of the sub-grade: Hill Cutting (40% weightage of 55.5%)	22.2%	Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 500 m.
(1.2) Earthwork up to top of the sub-grade: Construction of Subgrade (60% weightage of 55.5%)	33.3%	
(2) Sub-base Course	15.41%	
(3) Non bituminous Base course	8.24%	
(4) Bituminous Base course	0.71%	
(5) Wearing Coat	6.00%	
B.2- Reconstruction/New 8-Lane Realignment/Bypass (Rigid Pavement)		
(1) Earthwork up to top of the sub-grade	[Nil]	Unit of measurement is linear length. Payment of each stage shall be made on pro-rata basis on completion of a stage in full length or 5(five) km length, whichever is less.
(2) Sub-base Course	[Nil]	
(3) Dry Lean Concrete (DLC) Course	[Nil]	
(4) Pavement Quality Control (PQC) Course	[Nil]	
C.1- Reconstruction/New Service Road/ Slip Road (Flexible Pavement)		
(1) Earthwork up to top of the sub-grade	[Nil]	Unit of measurement is linear length. Payment of each stage shall be made on pro-rata basis on completion of a stage in full length or 5(five) km length, whichever is less.
(2) Sub-base Course	[Nil]	
(3) Non bituminous Base course	[Nil]	
(4) Bituminous Basecourse	[Nil]	
(5) Wearing Coat	[Nil]	
C.2- Reconstruction/New Service road (Rigid Pavement)		
(1) Earthwork up to top of the sub-grade	[Nil]	Unit of measurement is linear length. Payment of each stage shall be made on pro-rata basis on completion of a stage in full length or 5(five) km length, whichever is less.
(2) Sub-base Course	[Nil]	
(3) Dry Lean Concrete (DLC) Course	[Nil]	
(4) Pavement Quality Control (PQC) Course	[Nil]	

Stage of Payment	Percentage weightage	Payment Procedure

@ For example, if the total length of bituminous work to be done is 100 km, the cost per km of bituminous work shall be determined as follows:

$$\text{Cost per km} = P \times \text{weightage for road work} \times \text{weightage for bituminous work} \times (1/L)$$

Where,

P = Contract Price

L = Total length in km

Similarly, the rates per km for other stages shall be worked out accordingly.

Note: The length affected due to law and order problems or litigation during execution due to which the Contractor is unable to execute the work, may be deducted from the total project length for payment purposes. The total length calculated here is only for payment purposes and will not affect and referred in other clauses of the Contract Agreement.

1.3.2 Minor Bridges and Underpasses/Overpasses.

Procedure for estimating the value of Minor bridge and Underpasses/Overpasses shall be as stated in table 1.3.2:

Table 1.3.2

Stage of Payment	Weightage	Payment Procedure
1	2	3
A.1-Widening and repairs of Minor Bridges(length>6m<60m)	Nil	Cost of each minor bridge shall be determined on pro-rata basis with respect to the total linear length of the minor bridges. Payment shall be made on the completion of widening & repair works of a minor bridge
A.2- New Minor Bridges (length > 6m & < 60m)		
(1)Foundation + Sub-Structure: On completion of the foundation work including foundations for wing and return walls, abutments, piers up to the abutment/ pier cap.	Nil	Foundation: Cost of each minor bridge shall be determined on pro-rata basis with respect to the total linear length (m) of the minor bridges. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. Not less than 25% of the scope of foundation of each bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.
(2)Super-structure: On completion of the super-structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barriers, road, signs & markings, tests on completion etc. complete in all respect.	Nil	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super structure of at least one span in all respects as specified in the column of "Stage of Payment" in this sub-clause. In case of structures where pre-cast girders have been proposed by the Contractor, 50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be made on completion of

Stage of Payment	Weightage	Payment Procedure
		stage specified as above
(3) Approaches : On completion of approaches including Retaining walls, stone pitching, protection works complete in all and fit for use	Nil	Approaches: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of approaches in all respect as specified in the column of "Stage of Payment" in this sub-clause.
(4) Guide Bunds and River Training Works: On completion of Guide Bunds and river training works complete in all respects	Nil	Guide Bunds and River Training Works: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of Guide Bund sand River training Works in all respects as specified
B.1- Widening and repairs of underpasses/overpasses	[Nil]	Cost of each underpass/overpass shall be determined on pro-rata basis with respect to the total linear length of the underpasses/ overpasses. Payment shall be made on the completion of widening & repair works of a underpass/overpass.
B.2- New Underpasses/Overpasses		
(1) Foundation + Sub-Structure: On completion of the foundation work including foundations for wing and return walls, abutments, piers up to the abutment/pier cap.	[Nil]	Foundation: Cost of each Underpass/ Overpass shall be determined on pro- rata basis with respect to the total linear length (m) of the Underpasses/Overpasses. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. Not less than 25% of the scope of foundation of each Underpasses/ Overpasses. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.
(2) Super-structure: On completion of the super-structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barriers, road signs & markings, tests on completion etc. complete in all respect. Wearing Coat (a) in case of Overpass-wearing coat including expansion joints complete in all respects as specified and (b) in case of underpass- rigid pavement including drainage facility complete in all respects as specified.	[Nil]	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super- structure of at least one span in all respects as specified in the column of "Stage of Payment" in this sub-clause. In case of structures where pre-cast girders have been proposed by the Contractor, 50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be made on completion of stage specified as above
(3) Approaches: On completion of approaches including Retaining walls/ Reinforced Earth walls, stone pitching, protection works complete in all respect and fit for use.	[Nil]	Payment shall be made on pro-rata basis on completion of a stage in all respects as specified



1.3.3 Major Bridge works, ROB/RUB and Structures.

Procedure for estimating the value of Major Bridge works, ROB/RUB and Structures shall be as stated in table 1.3.3:

Table 1.3.3

Stage of Payment	Weightage	Payment Procedure
A.1- Widening and repairs of Major Bridges		
(1) Foundation	[Nil]	Foundation: Cost of each Major Bridge shall be determined on pro-rata basis with respect to the total linear length (m) of the Major Bridge. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the major Bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.
(2) Sub-structure	[Nil]	Sub-structure: Payment against sub- structure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of sub- structure of major bridge.
(3) Super-structure (including bearings)	[Nil]	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super- structure including bearings of at least one span in all respects as specified. In case of structures where pre-cast girders have been proposed by the Contractor, 50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be made on completion of stage specified as above
(4) Wearing Coat including expansion joints	[Nil]	Wearing Coat: Payment shall be made on completion of wearing coat including expansion joints complete in all respects as specified.
(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]	Miscellaneous: Payments shall be made on completion of all miscellaneous works like handrails, crash barriers, road markings etc. complete in all respects as specified.
(6) Wing walls/return walls	[Nil]	Wingwalls/return walls: Payments shall be made on completion of all wing walls/return walls complete in all respects as specified.
(7) Guide Bunds, River Training works etc.	[Nil]	Guide Bunds, River Training works: Payments shall be made on completion of all guide bunds/river training works etc. complete in all respects as specified.
(8) Approaches (including Retaining walls, stone pitching and protection works)	[Nil]	Approaches: Payments shall be made on pro-rata basis on completion of 10% of the scope of each stage.
A.2-New Major Bridges		
(1) Foundation	18.16%	Foundation: Cost of each Major Bridge shall be determined on pro-rata basis with respect to the total linear length (m) of the Major Bridge. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the major Bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.

Stage of Payment	Weightage	Payment Procedure
(2)Sub-structure	51.26%	Sub-structure: Payment against sub- structure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of sub- structure of major bridge.
(3)Super-structure(including bearings)	24%	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super- structure including bearings of at least one span in all respects as specified. In case of structures where pre-cast girders have been proposed by the Contractor, 50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be made on completion of stage specified as above
(4)Wearing Coat including expansion joints	2.72%	Wearing Coat: Payment shall be made on completion of wearing coat including expansion joints complete in all respects as specified.
(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	1.28%	Miscellaneous: Payments shall be made on completion of all miscellaneous works like handrails, crash barriers, road markings. complete in all respects as specified.
(6) Wing walls/return walls	[Nil]	Wing walls/return walls: Payments shall be made on completion of all wing walls/return walls complete in all respects as specified.
(7)Guide bunds, River Training works etc.	[Nil]	Guide Bunds, River Training works: Payments shall be made on completion of all guide bunds/river training works etc. complete in all respects as specified.
(8)Approaches(including Retaining walls, stone pitching and protection works)	2.58%	Approaches: Payments shall be made on pro-rata basis on completion of 10% of the scope of each stage.
B.1- Widening and repairs of		
(a)ROB (b)RUB		
(1) Foundations	[Nil]	Foundation: Cost of each ROB/RUB shall be determined on pro-rata basis with respect to the total linear length (m)of the ROB/RUB. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the ROB/RUB. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.
(2) Sub-Structure	[Nil]	Sub-structure: Payment against sub- structure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of sub- structure of ROB/RUB.
(3) Super-Structure (Including bearings)	[Nil]	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super- structure including bearings of at least one span in all respects as specified. In case of structures where pre-cast girders have been proposed by the Contractor, 50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be made on completion of stage specified as above
(4) Wearing Coat(a)in case of ROB-wearing coat including expansion joints complete in all respects as specified and (b) in case of RUB-rigid pavement under RUB	[Nil]	Wearing Coat: Payment shall be made on completion (a) in case of ROB-wearing coat including expansion joints complete in all respects as specified

Stage of Payment	Weightage	Payment Procedure
including drainage facility complete in all respects as specified		and (b) in case of RUB-rigid pavement under RUB including drainage facility complete in all respects as specified.
(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]	Miscellaneous: Payments shall be made on completion of all miscellaneous works like handrails, crash barriers, road markings etc. complete in all respects as specified.
(6) Wing walls/Return walls	[Nil]	Wingwalls/return walls: Payments shall be made on completion of all wing walls/return walls complete in all respects as specified.
(7) Approaches (Including Retaining walls, Stone Pitching and protection works)	[Nil]	Payments shall be made on pro-rata basis on completion of 20% of the total area.
B.2-NewROB/RUB		
(1) Foundation	[Nil]	Foundation: Cost of each ROB/RUB shall be determined on pro-rata basis with respect to the total linear length (m)of the ROB/RUB. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the ROB/RUB.
(2) Sub-structure	[Nil]	Sub-structure: Payment against sub- structure shall be made on pro-rata basis on completion of a stage i.e. Not less than 25% of the scope of sub- structure of ROB/RUB.
(3) Super-structure (including bearing)	[Nil]	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super- structure including bearings of at least one span in all respects as specified. In case of structures where pre-cast girders have been proposed by the Contractor,50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be made on completion of stage specified as above
(4)Wearing Coat (a) in case of ROB- wearing coat including expansion joints complete in all respects as specified and (b) in case of RUB-rigid pavement under RUB including drainage facility complete in all respects as specified	[Nil]	Wearing Coat: Payment shall be made on completion (a) in case of ROB-wearing coat including expansion joints complete in all respects as specified and (b) In case of RUB-rigid pavement under RUB including drainage facility complete in all respects as specified.
(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]	Miscellaneous: Payments shall be made on completion of all miscellaneous works like handrails, crash barriers, road markings etc. Complete in all respects as specified.
(6) Wing walls/Return walls	[Nil]	Wingwalls/return walls: Payments shall be made on completion of all wing walls/return walls complete in all respects as specified.
(7)Approaches (including Retaining walls/Reinforced Earth wall, stone pitching and protection works)	[Nil]	Payment shall be made on pro-rata basis on completion of a stage in all respects as specified
C.1-Wideningandrepairs of Elevated Section/ Flyovers/Grade Separators		
(1) Foundations	[Nil]	Foundation: Cost of each structure shall be determined on pro-rata basis with respect to the total linear length (m)of

Stage of Payment	Weightage	Payment Procedure
		<p>the structure. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the structure.</p> <p>In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.</p>
(2) Sub-Structure	[Nil]	Sub-structure: Payment against sub- structure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of sub- structure of structure.
(3) Super-Structure(Including bearings)	[Nil]	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super- structure including bearings of at least one span in all respects as specified. In case of structures where pre-cast girders have been proposed by the Contractor,50% of the stage payment shall be due and payable on casting of girders for each span and balance 50% of the stage payment shall be made on completion of stage specified as above
(4) Wearing Coat including expansion joints	[Nil]	Wearing Coat: Payment shall be made on completion of wearing coat including expansion joints complete in all respects as specified.
(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]	Miscellaneous: Payments shall be made on completion of all miscellaneous works like handrails, crash barriers, road markings etc. Complete in all respects as specified.
(6) Wing walls/Return walls	[Nil]	Wingwalls/return walls: Payments shall be made on completion of all wing walls/return walls complete in all respects as specified.
(7) Approaches (including Retaining walls/Reinforced Earth wall, stone pitching and protection works)	[Nil]	Payment shall be made on pro-rata basis on completion of a stage in all respects as specified
C.2- New Elevated Section/ Flyovers/Grade Separators		
(1) Foundations	[Nil]	<p>Foundation: Cost of each structure shall be determined on pro-rata basis with respect to the total linear length (m)of the structure. Payment against foundation shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the structure.</p> <p>In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.</p>
(2) Sub-Structure	[Nil]	Sub-structure: Payment against sub- structure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of sub- structure of structure.
(3)Super-Structure(Including bearings)	[Nil]	Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super- structure including bearings of at least one span in all respects as specified. In case of structures where pre-cast girders have been proposed by the Contractor,50% of the stage payment shall be due and payable on casting of girders foreach span and balance 50% of the stage payment shall be made on completion of stage specified as above

Stage of Payment	Weightage	Payment Procedure
(4)Wearing Coat including expansion joints	[Nil]	Wearing Coat: Payment shall be made on completion of wearing coat including expansion joints complete in all respects as specified.
(5) Miscellaneous Items like handrails, crash barrier, road markings etc.	[Nil]	Miscellaneous: Payments shall be made on completion of all miscellaneous works like handrails, crash barriers, road markings etc. complete in all respects as specified.
(6) Wing walls/Return walls	[Nil]	Wingwalls/return walls: Payments shall be made on completion of all wing walls/return walls complete in all respects as specified.
(7)Approaches (including Retaining walls/Reinforced Earth wall, stone pitching and protection works)	[Nil]	Payments shall be made on pro-rata basis on completion of 20% of the total area.

Note: (1) In case of innovate Major Bridge projects like cable suspension/cable stayed/ Extra Dozed and exceptionally long span bridges, the schedule may be modified as per site requirements before bidding with due approval of Competent Authority.

(2) The Schedule for exclusive tunnel projects may be prepared as per site requirements before bidding with due approval of Competent Authority.

1.3.4 Other works.

Procedure for estimating the value of other works done shall be as stated in table 1.3.4.

Table 1.3.4

Stage of Payment	Weightage	Payment Procedure
1	2	3
(2) Road side drains	20.344%	Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 10% (ten percent) of the total length.
(3) Road signs, markings, km stones, safety devices etc	5.035%	
(4) Project Facilities		Payment shall be made on pro rata basis for completed facilities.
a) Bus Bays	0.194%	
b) Truck Lay-byes	0.692%	
c) Passenger Shelter	0.08%	
(8) Protection Works		Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 10% (ten percent)of the total length.
(a) Retaining Wall	13.982%	
(b) Breast Wall	17.569%	
(c) Gabian Structure	17.203%	
(d) "W" : Metal Beam Crash Barrier	1.744%	
(e) Parapet Wall	3.815%	

Stage of Payment	Weightage	Payment Procedure
(9) Site Clearance & Dismantling	1.503%	Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 10% (ten percent) of the total length.
(10) Other Works (Protection Works (Seeding and Mulching, Turfing and Slope Protection with Soil Naling & Coir Mat)	16.873%	Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 10% (ten percent) of the total length.
(11) Utility Shifting	0.966%	Unit of measurement is as per completed activities. Cost per activity shall be determined on pro-rata basis as per its weightage with reference to total cost. Payment shall be made for completed activity.

2. Procedure for payment for Maintenance

2.1 The cost for maintenance shall be as stated in Clause 14.1.1.

2.2 Payment for Maintenance shall be made in quarterly instalments in accordance with the provisions of Clause 19.7.