

Schedule – C

(See Clause 2.1)

PROJECT FACILITIES

1 Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- a) Roadside Furniture;
- b) Tree Plantation;
- c) Others to be specified

2 Description of Project Facilities

Each of the Project Facilities is described below showing:

a) Toll Plaza : NIL

b) Road side Furniture

(i) Traffic Signs and Pavement Markings:

Traffic signs and pavement markings shall include road side signs, overhead signs, curve mounted signs and road marking along the project highway. The locations for these provisions shall be finalized as per manual.

(ii) Concrete Crash Barrier, Metal beam crash barrier, Separators (MS railings) wherever required as per manual.

(iii) Traffic Safety Devices wherever required

(iv) Boundary Stones

(v) Hectometer / Kilometer Stones

(vi) Fluorescent strips have to be provided at sites requiring safety and protection.

(vii) Overhead signs: To be provided at one locations i.e. at 60/585 as per IRC 67

(viii) Delineators and Studs: Nil

c) Pedestrian Facilities

Footpath on covered have been provided at the following stretches

SI No	Chainage from	Chainage to	Width of drain
1	52900	54750	1.0 m on both side
2	58550	58650	
3	60150	60585	

d) Landscaping and Tree Plantation: Nil

e) Truck lay byes: Nil

f) Bus-bays and Bus Shelter: Nil