

CORRIGENDUM NO.1(a)

Project Title: Construction and upgradation of existing road to 2-lane with paved shoulder of Bagrakot-Kafer section of NH-717A from Km. 0.000 to Km. 13.000 on EPC basis under SARDP-NE Phase 'Á' in the State of West Bengal (Package-IV A).

1. Reference: NIT & RFP Document uploaded on CPP Portal on 07.12.2018.
2. Tender ID: 2018_NHIDC_416435_1

S.No.	Clause No.	Existing Provision	Modified Provision
1.	Point 'vi', Table 1.3.4 'Other Works', Schedule-H	Retaining Wall and Breast Wall- 61.79%	Retaining Wall- 50.89% Breast Wall- 10.90%
2.	Clause 12.1, Schedule-B	<p>12.1 Slope Protection Work</p> <p>Describing the technical capability of the bidders related to execution of slope protection works for proper execution on ground has been incorporated as under:</p> <p>i. The contractor shall be responsible for accurate assessment of the actual requirement as per site situation and prepare design for slope protection and stabilization as per specification and standards stipulated in schedule-D and submit the same to the Authority's Engineer/Authority for review through the Proof Consultant and implement it accordingly thereafter</p> <p>ii. Any increase in quantity over and above the tentative quantity as mentioned in above table or through change in specifications will not be considered as change of scope. Therefore, Contractor shall make through investigation at site and assess the requirement of slope protection and slide prone zone and other safety feature at his own before submission of bid.</p> <p>iii. For executing any of the above type of slope protection works, the contractor should have the experience of having executed, in last 5 (five) financial years from the date of signing of Agreement, at least 40% quantity of that type of slope protection works and provide requisite certificates/documents to verify the same to the Authority/ Authority engineer.</p> <p>iv. If the Contractor does not have requisite experience for any/some of the above type of slope protection works, then he has to engage specialized</p>	Deleted

S.No.	Clause No.	Existing Provision	Modified Provision
		firm(s) as sub-contractor(s) who has/have successfully completed in last 5(five) financial years at least 40% quantity of such works. The contractor shall submit the credentials and the qualifying experience of the specialized sub-contractor(s) for approval of Authority before the commencement of such slope protection works.	
3.	Para Annexure-I, Schedule-D 3,	At location where hill cutting is required Breast wall to be provided upto 4m height and the hill surface/ slope to be protected / treated with Soil/ Rock nailing & High Strength Wire Mesh having of minimum diameter 3 mm twisted or Straight of high tensile steel wire as per IRC & BS specifications. The System should be tailor made according to the site conditions and requirements with accessories like Connection Clips / Press Claws / Shackles/ Boundary Ropes / Wire Rope Anchors etc. Equivalent / Higher Protection system will be Technically Evaluated by Approving Authority. The Final Type of product to be used shall be decided upon approval of final design / drawing as per IRC & BS specification.	Deleted
4.	Para 3 Schedule-D	NIL	The Contractor shall ensure maintaining plan/profile/x-sections approved by Authority's Engineer and any slope protection required shall be considered incidental to the original work with no extra payment/change of scope on this account.
5.	Clause-14 Schedule-B	NIL	Utility Shifting Details Drinking Water Supply Line for Bagrakot from Chainage 3.75 Km to 3.85 Km.
6.	Clause-10 Schedule-B	Compulsory Afforestation The number of Trees which are required to be planted by the contractor as compensatory afforestation should be as per Forest Conservation Act, twice the number of trees to be cut	Deleted
7	Clause-2 Intersection and Grade Separators of Schedule-B	2	2.12

63

/


Sandeep Kumar
GM(Tech.)