

Schedule - C

(See Clause 2.1)

Project Facilities

1. Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- (a) toll plaza[s];
- (b) roadside furniture; (c) pedestrian facilities;
- (d) truck lay-byes;
- (e) bus-bays and bus shelters;
- (f) rest areas; and
- (g) others to be specified

2. Description of Project Facilities

Each of the Project Facilities is described below:

(a) Toll Plaza: Nil

(b) Roadside Furniture:

The roadside furniture shall be provided in accordance with section 9.0 of the Manual of the standards and Specifications.

Sl. No.	Project Facility	Location	Design Standard	Other essential details
1	Traffic Sign & Pavement marking	Entire Length(As per Schedule B)	As per manual	
2	Km stone, Hectometer Stone, 5 th kilometre stone	Entire Length	As per manual	
3	Roadside Delineator, marker & Road Stud	As per Schedule B	As per manual	
4	Metal beam crash barrier	As per Schedule B	As per manual	

(c) Pedestrian Facilities:

Pedestrian facilities in the form of footpath cum drain shall be provided in the built up area (refer typical cross-section drawing). Pedestrian facilities shall be provided at the locations of urban sections in order to ensure safety of pedestrians while crossing in consultation with Authority.

(d) Truck Lay Bys:

Sl. No.	Proposed Chainage (km)
Nil	

(e) Busbays and Bus shelters:

Sl. No.	Proposed Chainage (km)	Remarks
1	283.300 (Bothside)	Fig. 12.3 of Manual
2	308.350 (Bothside)	Fig. 12.3 of Manual
3	309.400 (Bothside)	Fig. 12.3 of Manual
4	310.450 (Bothside)	Fig. 12.3 of Manual

(f) Rest areas: Nil

(g) Others:

Street Lighting

Street lighting shall be provides in the built up area.

Environment

The Project Highway during design, construction and maintenance during implementation period shall conform to the environmental rules and regulations in force. The Construction Contractor shall be responsible for the same.

Note: Provide adequate details of each Project Facility to ensure their design and completion in accordance with the project-specific requirements and the provisions of the Manual.