

Schedule - C

(See Clause 2.1)

Project Facilities

1. Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- (a) Toll plaza;
- (b) Road side furniture;
- (c) Street lighting;
- (d) Pedestrian facilities;
- (e) Tree plantation;
- (f) Truck lay-byes;
- (g) bus-bays and bus shelters;
- (h) rest areas ;and
- (i) others to be specified

2. Description of Project Facilities

Each of the Project Facilities is described below:

- (a) Toll Plaza

Toll plaza shall be designed as per the guidelines of the manual and it is provided at following locations: -

Sl. No.	Location
	NIL

- (b) Road side Furniture

The roadside furniture shall include the provision of the;

- i. Traffic Signs

Traffic signs include roadside signs, overhead signs, curb mounted signs etc provided for the entire Project Highway as per Manual.

ii. Pavement Markings

Pavement markings shall cover road marking provided for the entire Project Highway as per Manual.

iii. LED Traffic Blinkers

LED Traffic Blinker signal provided for entire project as per Manual.

iv. Delineators

Delineators for the entire Project Highway at the locations as suggested in IRC Manual.

v. Boundary stones

For the entire Project Highway as suggested in relevant IRC Manual.

vi. Hectometer / Kilometer stones

For the entire Project Highway as suggested in relevant IRC Manual.

(c) Street Lighting

Lighting shall be provided at the following locations:

- i. Lighting shall be provided at flyover, built up areas, bus stops, and as per manual recommended in Schedule D.
- ii. High Mast Lighting shall be provided at Major Junction,

(d) Pedestrian facilities;

Pedestrian facilities shall be provided at the locations of urban sections in order to ensure safety of pedestrians while crossing in consultation with NHAI and as per manual

(e) Tree plantation;

Landscaping and Tree plantation shall be provided. The location for these provisions shall be finalized in consultation with Independent Engineer

(f) Truck lay-byes;

NIL

(g) bus-bays and bus shelters;

Bus Shelters shall be provided at locations given below:

Sl No.	Design Chainage (km)			Lengths (m)				Side	Location
	Start	Center	End	Start Taper	Straight	End Taper	Total		
1	428592	428700	428807	100	15	100	215	LHS	Dergaon
2	428707	428815	428922	100	15	100	215	RHS	Dergaon
3	432692	432800	432907	100	15	100	215	LHS	Negheriting
4	432807	432915	433022	100	15	100	215	RHS	Negheriting
5	436692	436800	436907	100	15	100	215	RHS	Balijan
6	436807	436915	437022	100	15	100	215	LHS	Balijan

(h) rest areas

NIL

Note: Provide adequate details of each Project Facility to ensure their design and completion in accordance with the project-specific requirements and the provisions of the Manual.