

Schedule – C

(See Clause 2.1)

PROJECT FACILITIES

1. Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- a) Roadside Furniture;
- b) Tree Plantation;
- c) Others to be specified

2. Description of Project Facilities

Each of the Project Facilities is described below showing:

a) Toll Plaza : NIL

b) Road side Furniture

(i) Traffic Signs and Pavement Markings:

Traffic signs and pavement markings shall include road side signs, overhead signs, curve mounted signs and road marking along the project highway. The locations for these provisions shall be finalised as per manual.

(ii) Concrete Crash Barrier, Metal beam crash barrier, Separators (MS railings) wherever required as per manual.

(iii) Traffic Safety Devices wherever required

(iv) Boundary Stones

(v) Hectometer / Kilometer Stones

(vi) Traffic Blinker Signal (L.E.D) shall be provided at all At-grade junctions, median opening, schools, hospitals, police station, places of worship and institutional buildings etc.

(vii) Overhead signs: To be provided at two locations i.e. at 0/00 and 17/000 as per IRC 67

For rehabilitation and up-gradation of Saiphai - Bagha Bazar Road from Bagha Bazar (0/000 km) to Saiphai(17/042 km) to intermediate & two lane carriageway in the State of Assam and Mizoram

(viii) Delineators and Studs: Nil

c) Pedestrian Facilities

Footpath in the built up sections to be provided.

d) Landscaping and Tree Plantation

Tree plantation shall be taken up along the project road after due construction.

e) Truck lay bays:

Nil

f) Bus-bays and Bus Shelter:

Nil