

VOLUME – II
PERCENTAGE BOQ

Validate

Print

Help

[View BoQ](#)

Tender Inviting Authority: NHIDCL

Name of Work: Repair and Maintenance of National Highway (NH 37) between Numaligarh to Jorhat (Km. 402.500 to Km. 453.000) (Percentage Rate and Work Order Basis)

Contract No: NHIDCL/RO-NE/AS/Maint./NH37/2017-18/6

Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	5	6	53	55
1	Water Bound Macadam for the pot holes filling	Nos	0.00	4409212.50	INR Forty Four Lakh Nine Thousand Two Hundred & Twelve and Paise Fifty Only
2	Prime Coat	Nos	0.00	785400.00	INR Seven Lakh Eighty Five Thousand Four Hundred Only
3	Tack coat	Nos	0.00	1948100.00	INR Nineteen Lakh Forty Eight Thousand One Hundred Only
4	Bituminous Macadam for pot hole filling	Nos	0.00	8876175.00	INR Eighty Eight Lakh Seventy Six Thousand One Hundred & Seventy Five Only
5	Bituminous Macadam for overlay	Nos	0.00	59174500.00	INR Five Crore Ninety One Lakh Seventy Four Thousand Five Hundred Only
6	Semi Dense Bituminous	Nos	0.00	40921650.00	INR Four Crore Nine Lakh Twenty One Thousand Six Hundred & Fifty Only

	Concrete				
7	Road Marking	Nos	0.00	1485000.00	INR Fourteen Lakh Eighty Five Thousand Only
Total in Figures				117600037.50	INR Eleven Crore Seventy Six Lakh &Thirty Seven and Paise Fifty Only
Quoted Rate in Figures		Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only			

NOTE: Bidder has to quote % above or below and quoted rates in figures & words will be auto generated which shall be binding on the bidder to agree the amount to work.

[Validate](#)[Print](#)[Help](#)[Wise BoQ](#)

Tender Inviting Authority: NHIDCL

Name of Work: Repair and Maintenance of National Highway (NH 37) between Numaligarh to Jorhat (Km. 402.500 to Km. 453.000) (Percentage Rate and Work Order Basis)

Contract No: NHIDCL/RO-NE/AS/Maint./NH37/2017-18/6

Bidder Name :	
------------------	--

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Water Bound Macadam for the pot holes filling Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surfaces, backfilling the pot holes with WBM material. (thickness 75 mm in one layer)	1575.00 0	cum	2799.50	4409212.50	INR Forty Four Lakh Nine Thousand Two Hundred & Twelve and Paise Fifty Only
2	Prime Coat: Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.60 kg/sqm using mechanical means.	21000.0 00	sqm	37.40	785400.00	INR Seven Lakh Eighty Five Thousand Four Hundred Only

3	Tack coat: 'Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom	161000.0000	sqm	12.10	1948100.00	INR Nineteen Lakh Forty Eight Thousand One Hundred Only
4	Bituminous Macadam for pot hole filling Providing and laying dense bituminous macadam (thickness 50mm) with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction.	1050.000	cum	8453.50	8876175.00	INR Eighty Eight Lakh Seventy Six Thousand One Hundred & Seventy Five Only

5	<p>Bituminous Macadam for overlay Providing and laying dense bituminous macadam (thickness 50mm) with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction.</p>	7000.00 0	cum	8453.50	59174500.00	INR Five Crore Ninety One Lakh Seventy Four Thousand Five Hundred Only
6	<p>Semi Dense Bituminous Concrete-25 mm Providing and laying dense bituminous concrete with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder@ 4.5 to 5 % of mix and filler (cement) transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction.</p>	3500.00 00	cum	11691.90	40921650.00	INR Four Crore Nine Lakh Twenty One Thousand Six Hundred & Fifty Only

7	Road Marking: Road marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface - Providing and laying of Hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads @250 gms per sqm, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. the finished surface to be level, uniform and free from streaks and holes.	1800.00 00	cum	825.00	1485000.00	INR Fourteen Lakh Eighty Five Thousand Only
Total in Figures					117600037.50	INR Eleven Crore Seventy Six Lakh &Thirty Seven and Paise Fifty Only
Quoted Rate in Words		INR Eleven Crore Seventy Six Lakh &Thirty Seven and Paise Fifty Only				