

VOULME – II

PERCENTAGE BOQ

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: NHIDCL

Name of Work: Patch & Pot Hole Repairing and Strengthening of NH-38 from km 20.00 to km 53.00 in the state of Assam (Percentage Rate and Work Order Basis)

Contract No: NHIDCL/Assam/R&M/NH-38/2018-19/01

Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

| NUMB ER # | TEXT # | TEXT # | NUMBER | NUMBER # | TEXT # |
|-----------|---|--------|----------------|----------------------------|---|
| Sl. No. | Item Description | Units | Estimated Rate | TOTAL AMOUNT Without Taxes | TOTAL AMOUNT In Words |
| 1 | 2 | 5 | 6 | 53 | 55 |
| 1 | Granular Sub-base with Close Graded Material | cum | 0.00 | 644675.50 | INR Six Lakh Forty Four Thousand Six Hundred & Seventy Five and Paise Fifty Only |
| 2 | Water Bound Macadam for the pot holes filling | cum | 0.00 | 913020.50 | INR Nine Lakh Thirteen Thousand & Twenty and Paise Fifty Only |
| 3 | Prime Coat: | sqm | 0.00 | 163446.50 | INR One Lakh Sixty Three Thousand Four Hundred & Forty Six and Paise Fifty Only |
| 4 | Tack coat: | sqm | 0.00 | 185183.76 | INR One Lakh Eighty Five Thousand One Hundred & Eighty Three and Paise Seventy Six Only |
| 5 | Bituminous Macadam for pot hole filling | cum | 0.00 | 3166606.26 | INR Thirty One Lakh Sixty Six Thousand Six Hundred & Six and Paise Twenty Six Only |

| | | | | | |
|-------------------------------|--------------------------------------|----------------------|------|-------------------|--|
| 6 | Semi Dense Bituminous Concrete-25 mm | cum | 0.00 | 2178946.00 | INR Twenty One Lakh Seventy Eight Thousand Nine Hundred & Forty Six Only |
| 7 | Surface Drains in Soil | mtr | 0.00 | 48384.00 | INR Forty Eight Thousand Three Hundred & Eighty Four Only |
| Total in Figures | | | | 7300262.52 | INR Seventy Three Lakh Two Hundred & Sixty Two and Paise Fifty Two Only |
| Quoted Rate in Figures | | Select | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | INR Zero Only | | | |

Validate

Print

Help

Item Wise BoQ

Tender Inviting Authority: NHIDCL

Name of Work: Patch & Pot Hole Repairing and Strengthening of NH-38 from km 20.00 to km 53.00 in the state of Assam (Percentage Rate and Work Order Basis)

Contract No: NHIDCL/Assam/R&M/NH-38/2018-19/01

Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | TEXT # |
|----------|---|----------|--------|----------------|----------------------------|--|
| Sl. No. | Item Description | Quantity | Units | Estimated Rate | TOTAL AMOUNT Without Taxes | TOTAL AMOUNT In Words |
| 1 | 2 | 4 | 5 | 6 | 53 | 55 |
| 1 | Granular Sub-base with Close Graded Material By Mix in place method (Construction of granular sub-base by providing close graded material , spreading in uniform layers with motor grader on prepared surface , mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achive the desired density, complete as per cl.401(including cost of test of materials at site and laboratory as directed by dept.) For grading material -III | 350.00 | cum | 1841.93 | 644675.50 | INR Six Lakh Forty Four Thousand Six Hundred & Seventy Five and Paise Fifty Only |
| 2 | Water Bound Macadam for the pot holes filling Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surfaces, backfilling the pot holes with WBM material. (thickness 75 mm in one layer) | 350.00 | cum | 2608.63 | 913020.50 | INR Nine Lakh Thirteen Thousand & Twenty and Paise Fifty Only |
| 3 | Prime Coat: Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.60 kg/sqm using mechanical means. | 4690.00 | sqm | 34.85 | 163446.50 | INR One Lakh Sixty Three Thousand Four Hundred & Forty Six and Paise Fifty Only |

| | | | | | | |
|-----------------------------|---|--|-----|----------|------------------------|---|
| 4 | Tack coat: Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom | 1641 7.00 | sqm | 11.28 | 185183.76 | INR One Lakh Eighty Five Thousand One Hundred & Eighty Three and Paise Seventy Six Only |
| 5 | Bituminous Macadam for pot hole filling Providing and laying bituminous macadam (thickness 50mm) with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction. | 402.0 0 | cum | 7877.13 | 3166606.26 | INR Thirty One Lakh Sixty Six Thousand Six Hundred & Six and Paise Twenty Six Only |
| 6 | Semi Dense Bituminous Concrete-25 mm Providing and laying semi dense bituminous concrete with Hot Mix Plant using crushed aggregates of specified grading, premixed with bituminous binder@ 4.5 to 5 % of mix and filler (cement) transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the reqd. grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction. | 200.0 0 | cum | 10894.73 | 2178946.00 | INR Twenty One Lakh Seventy Eight Thousand Nine Hundred & Forty Six Only |
| 7 | Surface Drains in Soil Construction of unlined surface drains of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions to the requirement of Clause 301 and 309. Excavated material to be used in embankment within a lead of 50m (Average lead 25 m) A. Mechanical means | 800.0 000 | mtr | 60.48 | 48384.00 | INR Forty Eight Thousand Three Hundred & Eighty Four Only |
| Total in Figures | | | | | 7300262.5 2 | INR Seventy Three Lakh Two Hundred & Sixty Two and Paise Fifty Two Only |
| Quoted Rate in Words | | INR Seventy Three Lakh Two Hundred & Sixty Two and Paise Fifty Two Only | | | | |

NOTE: Bidder has to quote % above and below and quoted rates in figures & words will be auto generated which shall be binding on the agree the amount to work