



परियोजना प्रबंधन इकाई -खोवाई

राष्ट्रीय राजमार्ग और अवसंरचना विकास निगम लिमिटेड

(सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)

PMU- Khowai

National Highways & Infrastructure Development Corporation Ltd.

(Ministry of Road Transport & Highways, Govt. of India)



BHARATMALA  
ROAD TO PROSPERITY

भारत सरकार का उपक्रम

A GOVT OF INDIA UNDERTAKING

NHIDCL/PMU-Khw/21(28)/2021-22/ 1199

Date - 23.11.2022


## NOTICE INVITING QUOTATION

**Name of the Work:** Emergent repair of bailey bridge located at Chebri mauja on the road section of Khowai to Teliamura (NH-208) in the state of Tripura.

1. National Highway and Infrastructure Development Corporation Limited (hereinafter called "the Employer") invites NIQ on item rate basis for the works mentioned below from the experienced Road/Bridge Contractors/Firms/Organization excluding those firms who have been declared as non-performing by MoRT&H/NHAI/NHIDCL or the firms those are blacklisted/debarred for specified period by MoRT&H/NHAI/NHIDCL.

Sl. No.	Name of Work/Contract Packager
1	Emergent repair of bailey bridge located at Chebri mauja on the road section of Khowai to Teliamura (NH-208) in the state of Tripura.

2. Date of Publishing on Notice Board of PMU-Khowai, SO-Teliamura & RO-Agartala: 23.11.2022.
3. Last date of submission of quotations on 25.11.2022 before 17:00 Hrs.
4. Work has to be completed in 30 days from the date of commencement of work i.e. from 23.11.2022. The quantity to be executed is at Annexure-I. Rate of each item are requested to be quoted in the enclose format (Annexure-I).
5. The site for the work is available.
6. The interested bidder can submit quotations for the same at 3 locations i.e. PMU-Khowai, NHIDCL, 2<sup>nd</sup> floor (C/o Jahar Nag), Ganki, Khowai, Tripura - 799202 / NHIDCL-RO-Agartala, 3<sup>rd</sup> floor, UD Bhavan, Sakuntala Road extension, Agartala, Tripura / SO-Teliamura, 2<sup>nd</sup> floor, Rani Das Building, AA Road, Above ICICI Bank, Teliamura, Tripura.
7. NHIDCL reserves the right to accept/reject any or all the NIQ without assigning any reason thereof.

  
(R.K Tindwal)  
General Manager (Project)

**National Highways Infrastructure & Development Corporation Limited (NHIDCL), TRIPURA**

Name of work: Emergent repair of bailey bridge located at Chebri mauja on the road section of Khowai to Teliamura (NH-208) in the state of Tripura in the FY 2022-23

Sl.No	Description of item	Quantity	Unit	Rate (In Rupees)	Amount (In Rupees)
1	Item Sl.No. 13.1. : Brick masonry work in cement mortar in substructure complete excluding pointing & plastering, as per drawing & MoRT&H technical specification Clause 1300, 2200. In 1:4 Cement Mortar.	144.38	Cum		
2	Item Sl.No. 13.3 : Plastering with cement mortar 15 mm thick on brickwork in substructure as per MoRT&H technical specification Clauses 1300 & 2200. I. In 1:4 cement mortar.	150.00	Sqm		
3	Item Sl.No. 13.4 : Plain/reinforced cement concrete in substructure complete including formwork as per drawing & MoRT&H technical specification Clauses 1500, 1700, 2200. (including centering, shuttering , staging etc. but excluding reinforcement). I. PCC M 15 Grade (upto 5 m height)	12.25	Cum		
4	Item Sl.No. 3.13: Excavation for structure Earthwork in excavatuion of foundation of structures per drawing and technical specification including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter,dressing of sides and bottom and utilising the remaning earth locally for road work as per MoRT&H Specifation Clauses of section 300. i. Ordinary Soil A By manual means (upto 3m depth)	31.00	Cum		
5	Item Sl.No. M-179. Steel joists ISMB (200x100x75).	1.45	Tonne		
Total=					₹ 0

*hand*